

# PERFORMANCE RESULTS

Sotralentz  
3 rue de Bettwiler  
F-67320 Drulingen

represented  
by

Tricel

## EN 12566-1

Part 1: Prefabricated septic tanks

Results corresponding to the Irish National Annex for IS EN 12566-1

### Vento Septic Tank

Nominal capacity (treatment capacity)	3 m <sup>3</sup> (3,036 litres) 4 m <sup>3</sup> (4,255 litres) 5 m <sup>3</sup> (5,009 litres)
Material	polyethylene
Hydraulic efficiency (Annex B)	99.88 %
Watertightness (water test)	pass
Crushing resistance (pit test)	pass (also wet conditions)
Durability	pass

Performance tested by:

**PIA – Prüfinstitut für Abwassertechnik GmbH**  
(PIA GmbH)  
Hergenrather Weg 30  
52074 Aachen, Germany

This document replaces neither the declaration  
of conformity nor the CE marking.



Notified Body  
No.: 1739



Certified according to  
ISO 9001:2008



Prüfinstitut für Abwassertechnik GmbH  
*Geprüft - bestet - testet*

Elmar Lancé

May 2014