



Prüfinstitut für
Abwassertechnik
GmbH

PERFORMANCE RESULTS

Sotralentz
3 rue de Bettwiller
F-67320 Drulingen

represented
by

Tricel (Killarney)
Ballyspillane INd Est
Killarney
Co.Kerry

EN 12566-1

Part 1: Prefabricated septic tanks

Results corresponding to the Irish National Annex for IS EN 12566-1

Vento Septic Tank

Nominal capacity (treatment capacity)	3 m ³ (3,036 litres) 4 m ³ (4,255 litres) 5 m ³ (5,009 litres)
Material	polyethylene
Hydraulic efficiency (Annex B)	99.88 %
Watertightness (water test)	pass
Crushing resistance (pit test)	pass (also wet conditions)
Durability	pass

Performance tested by:

PIA – Prüfinstitut für Abwassertechnik GmbH
(PIA GmbH)
Hergenrather Weg 30
52074 Aachen, Germany

This document replaces neither the declaration
of conformity nor the CE marking.



Notified Body
No.: 1739



Certified according to
ISO 9001:2008



Prüfinstitut für Abwassertechnik GmbH
geprüft - tested - testé

Elmar Lancé

May 2014